

I.J. Johnson,
59 Leicester Street,
Leamington Spa.

27th November 2009

ST PAULS CHURCH

QUOTATION : CRECHE, HERITAGE & CHILDREN'S TOILET

Creche and Heritage Rooms – Removal and Installation of New Low Level Cupboards and Worktops

Existing built-in cupboards and worktops to be taken out and removed from site, existing stainless steel sink units to be retained. All service pipework, drainage and water supplies to be removed.

Install new, standard double sink unit and worktop with new stainless steel single sink/drainer complete with mixer taps, waste and bottle trap, connected to existing. Worktop to be provided with up stand at rear against existing panelling and silicone sealed to prevent water ingress.

Install new, standard double sink unit and worktop at lower level, 700mm above finished floor level with new worktop and existing stainless steel sink, cut and fitted into new worktop, complete with cold water tap only, waste and bottle trap, connected to existing waste pipe.

Provide new instant electric water heater to provide hot water supply to both high level sink units to both rooms.

Worktop to extend approx., 1M between new base unit and wall and infilled at front around existing heater extract.

Remove all pinboards etc., from walls, and make good, ready for decoration, (decorating by others).

NB: Any additional work to existing panelling that is at present hidden, and the possibility of repair/levelling solution to existing floor surfaces, and other unknowns has not been included.

Children,s Toilet

Install new child friendly wash hand basin at lower level, complete with mixer taps, waste and plug, and connect waste to existing, supplies taken from existing.

Remove existing wc pan and cistern and install new 'junior pan and seat' complete with cistern utilising existing waste and supplies, making good where necessary.

Remove existing door, replace with ash faced door in existing frame, new ironmongery and locking devise at high level with thumb screw access.

All the above £2,950.00 (vat incl.)

Signed

Date